12. The deposit of the contractor will be returned one month after the expiry of the contract period if the terms of the contract as per tender notification are fulfilled.

FORM OF TENDER.

Sl. No.	Name of provision	Quantity	Rate	Remarks

H. S. RANGACHAR,
District Forest Officer.

ENGINEERING DEPARTMENT.

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 3rd January 1940.

The attention of the public is hereby invited to the detailed notification calling for tenders for constructing first floor of Chamber of Commerce, Bangalore, published on pages 57-59, Part VI of the *Mysore Gazette*, dated 11th January 1940. The last date of tender is 26th January 1940.

Abstract Notification dated 5th January 1940.

The attention of the public is hereby invited to the detailed notification calling for tenders for constructing additional rooms to the Kannada Boys' Middle School at new Sawar Lines, Bangalore, published on pages 60-61, Part VI of the *Mysore Gazette*, dated 11th January 1940. The last date of tender is 29th January 1940.

M. K. RAJAM IYENGAR,
Executive Engineer.

BANGALORE DIVISION.

Notification dated 6th January 1940.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for the maintenance work to Jigani Major Tank, Reg. No. 145 of Anekal Taluk, published on pages 2510-11 of Part VI of the *Mysore Gazette*, dated 14th December 1939 and to inform that the last day for the receipt of the tender is extended from 23rd December 1939 to 26th January 1940.

Duplicate challan for having credited into the Treasury the deposit amount of Rs. 125 should accompany each tender.

Abstract Notification dated 5th January 1940.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for restoring and improving Araladibbe Minor Tank, Reg. No. 257 of Nelamangala Taluk, published on pages 61-64 of Part VI of the *Mysore Gazette*, dated 11th January 1940.

The last date for the receipt of the tender is 2 P.M. on 27th January 1940. Duplicate challan for having credited the deposit amount of Rs. 170 into the Treasury under "17 (*a*) P. W. Deposits" should accompany each tender.

Abstract Notification dated 5th January 1940.

The attention of the public is hereby invited to the detailed notification inviting sealed tenders for constructing a building for the Town Hall at Devanahalli, published on pages 64-66 of Part VI of the *Mysore Gazette*, dated 11th January 1940.

The last date for the receipt of the tender is 2 P.M. on 27th January 1940. Duplicate challan for having credited the deposit amount of Rs. 410 into the Treasury under "17 (*a*) P. W. Deposits" should accompany each tender.

Notification dated 10th January 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 3rd February 1940, for constructing a masonry anecut at 1/13th mile of Madras-Cannanore Road, Kengeri side.

2. Tenders in the prescribed form obtainable on payment of four annas per form from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for constructing a masonry anecut at 1/13th mile of Madras-Cannanore Road, Kengeri side." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited into the Treasury the deposit amount of Rs. 160 under 17 (a) P. W. Deposits in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 3rd February 1940 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 per each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Re. 1-0-0 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities for constructing a masonry anecut in 1—13 of Madras-Cannanore Road, Kengeri side.

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted	
					Figures	Words
			Rs. a. p.		Rs.	Rs.
1	Earthwork excavation for foundation in different soils	C.yd.	0 3 0	276		
2	Benching rock 6″ deep	S.ft.	0 6 0	520		
3	Cement concrete 1 : 4 : 8 in proportion in layers of 6″ deep including tamping ..	C.ft.	0 6 0	1,080		
4	Rubble masonry with face stones in cement mortar 1 : 6 in proportion for foundation and superstructure	,,	0 5 0	6,292		
5	Cement concrete coping to a depth of 3″ (1 : 2 : 4) with ½″ jelly including plastering with cement, etc., complete	,,	0 12 0	286		
6	Cement pointing	Sqr.	3 8 0	21.56		
7	Revetment with size stones with jelly backing and jelly wedging, etc., including required lead and lift	C.yd.	1 8 0	45		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 2nd January 1940.

The attention of the public is invited to the notification, calling for tenders for the work of constructing drains in Konanur Town for the year 1939-40, published in pages 46-47, Part VI of the *Mysore Gazette*, dated 4th January 1940.

The last date of receiving tenders is fixed on 22nd January 1940.

Notification dated 9th January 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 31st January 1940, for the work of constructing 1st stage drains in Bhadravati Old Town. An approximate estimate of quantities is given below. These quantities are not guaranted. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer on a payment of annas four per each form. No tender not in the prescribed form will be accepted. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 425 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for the work of constructing 1st stage drains in Bhadravati Old Town," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Estimate of the approximate quantities for the work of constructing 1st stage drains in Bhadravati Old Town.

Sl. No.	Particulars	Unit	Quantity	Rate
	I. *Constructing a septic tank with a screening chamber.*			Rs. a. p.
1	Earthwork excavation	C.yd.	8	
2	Burnt stone jelly cement concrete 1 : 2 : 4	C.ft.	192	
3	Cement plastering in the proportion of 1 : 2 one inch thick including rounding corner	Sqr.	1·12	
4	Constructing cement concrete drain including benching and plastering inside the chamber as per design	S.ft.	72	
5	Inserting and fixing pipe inlet and outlet	No.	2	
6	Providing and fixing wrought iron screen as per design	S.ft.	18	
7	Providing and fixing cast iron steps	No.	1	
	II. *Septic Tank.*			
1	Earthwork excavation	C.yd.	675	
2	Cement concrete with burnt stone jelly in the proportion 1 : 2 : 4	C.ft.	5,571	
3	One inch thick cement plastering (1 : 2) including round corners	Sqr.	49·67	
4	Reinforced concrete sheet 6" thick for hanging baffle walls including cement plastering and fixing	S.ft.	299	
5	Providing and fixing C. I. steps	No.	20	
6	Providing and fixing valves 1' in diameter with pipe, etc., complete at the bed of removal of sludge	No.	4	
7	Constructing semi-circular drain to carry the sludge at bottom in cement concrete and cement plastering including earthwork, etc., complete as per design	R.ft.	50	
8	Making sludge platforms as per design	No.	2	

Sl. No.	Particulars	Unit	Quantity	Rate
				Rs. a. p.
9	Constructing inlet drains between screening chamber and septic tank in cement concrete and cement plastering earthwork, etc., complete	R.ft.	18	
10	Providing and fixing pipe inlets with closing valves	No.	2	
	III. *Constructing a septic tank at the southern bank of bhadra River with screening chamber.*			
	Screening Chamber.			
1	Earthwork excavation	C.yd.	4	
2	Cement concrete (1 : 2 : 4) with broken jelly	C.ft.	96	
3	One inch thick cement plastering (1 : 2) including rounding corners	Sqr.	0·88	
4	Providing and fixing pipe inlet and outlet	No.	2	
5	Providing and fixing a wrought iron screen as per design ..	S.ft.	14	
6	Providing and fixing cast iron steps	No.	1	
	Septic Tank.			
1	Earthwork excavation	C.yd.	154	
2	Cement concrete (1 : 2 : 4) with broken burnt stone jelly ..	C.ft.	1,960	
3	Reinforced concrete sheet 6″ thick for hanging baffle ..	S.ft.	70	
4	One inch thick cement plastering in the proportion of 1 : 2 ..	Sqr.	12·26	
5	Providing and fixing C. I. steps	No.	14	
6	Providing and fixing pipe inlets	,,	2	
	IV. *Constructing Drains.*			
	Constructing semi-peg top section drain with burnt stone jelly concrete in cement mortar in the proportion of 1 : 2½ : 5 and cement plastering ½″ thick for the exposed surface in the proportion of 1 : 2 for the exposed surface including earthwork excavation, etc., complete as per design—			
	Design of 6″(6) section	R.ft.	1,020	
	Design of 7″(8) section	,,	290	

K. S. HUTCHA RAO,
Sanitary Engineer.

KOLAR DIVISION.

Abstract Notification dated 31st December 1939.

The attention of the public is invited to the detailed notification dated 30th December 1939, published on pages 41-43, Part VI of the *Mysore Gazette*, dated 4th January 1940 regarding construction of Sri Sappalammadevaru Temple at Thornahalli village, Malur Taluk.

The last date for receiving tenders is 26th January 1940 up to 2 P.M.

Abstract Notification dated 9th January 1940.

The attention of the public is invited to the detailed notification dated 9th January 1940, published on pages 100-103, Part VI of the *Mysore Gazette*, dated 11th January 1940, regarding tenders for restoring Muniganahalli Minor Tank, Reg. No. 666-407, in Chintamani Taluk.

The last date for receiving tenders is 29th January 1940, up to 2 P.M.

C. R. IYENGAR,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 2nd January 1940.

The attention of the public is drawn to the notification calling for tenders for restoring Kalkote Tank, Reg. No. 19, Sira Taluk, published on pages 43-46, Part VI of the *Mysore Gazette*, dated 4th January 1940.

2. The tenders will be received by the Executive Engineer up to 2 P.M. on 22nd January 1940.

3. The earnest money required for the work is Rs. 450 which should be credited to the treasury to "17 (*a*) P. W. Deposits" and the relative chellan enclosed.

Abstract Notification dated 3rd January 1940.

The attention of the public is drawn to the Notification calling for tenders for collection of burnt stone jelly in miles 71 to 98 (both inclusive) of Bangalore-Honnavar road, published in pages 67-68, Part VI of the *Mysore Gazette*, dated 11th January 1940.

2. The tenders will be received by the Executive Engineer up to 2 P.M. on 26th January 1940.

3. The earnest money required for the work is Rs. 50 for each section of mile, which should be credited to the treasury to "17 (*a*) P. W. Deposits" and the relative chellan enclosed.

Notification dated 11th January 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 2nd February 1940, for restoring the breached Kagglodu Major Tank, Reg. No. 146 of Sira Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four for each form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury chellan for Rs. 315 credited to the Treasury to "17 (*a*) P. W. Deposits," as earnest money, and be superscribed "Tender for restoring the breached Kagglodu Major Tank, Reg. No. 146 of Sira Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per current schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words, as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than the estimated rate will not be accepted.

Details of Abstract estimate for restoring the breached Kagglodu Major Tank, Reg. No. 146 of Sira Taluk.

No.	Description of work	Unit	Quantity	Rate
	I.—*Bund R. L.* 55.00.			Rs. a. p.
1	Clearing jungle	L. S.		
2	Cutting grips, etc.	"		
3	Earthwork to bund including watering and tamping, etc., complete	C.yd.	7,852	0 4 0
4	Rough stone work new with lead of 2 miles	"	191	1 8 0
5	Turfing	S.yd.	9,850	0 0 9
6	Gravelling the top of bund with watering and consolidation (Gravel to be used from approach cutting of waste weir)	C.yd.	550	4 0 0

No.	Description of work	Unit	Quantity	Rate
				Rs. a. p.
	II. *Breach Filling.*			
1	Clearing silt	L. S.	...	..
2	Cutting grips and steps, etc.	,,	..	..
3	Earthwork excavating foundation	C.yd.	1,151	0 3 0
3*a*	Earthwork refilling with consolidation (⅓ good gravel and ⅔ good earth to be used got from draft and approach of weir)	,,	1,151	0 7 0
4	Earthwork to breach with watering and consolidation (⅓ good gravel and ⅔ good earth to be used got from approach and draft cutting of weir)	,,	2,825	0 7 0
5	Rough stone work new with a lead of 2 miles	,,	129	1 8 0
6	Removing and resetting old stones with new jelly backing	,,	129	0 12 0
7	Turfing	S.yd.	774	0 0 9
8	Gravel backing behind revetment (gravel to be got from draft and approach cutting at weir)	C.yd.	200	0 5 0
	III. *Waste weirs.*			
1	*Left waste weir R. L.* 49.50— Earthwork excavation in ordinary soil cutting approach and draft to R. L. 49.50 and using soil to bund	C.yd.	212	0 3 0
2	*Right waste weir R. L.* 50.00— Earthwork excavation in hard gravel and strong soil and using to gravel backing, bund, etc.	C.yd.	3,400	0 4 0

Notification dated 12th January 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 9th February 1940, for raising the weirs of Haldodderi Major Tank, Reg. No. 211 of Sira Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1941.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer on payment of annas four for each form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury chellan of Rs. 450 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for raising the weirs of Haldodderi Major Tank, Reg. No. 211 of Sira Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per current schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Details of abstract estimate for raising the weir of Haldodderi Tank, Register No. 211 to R. L. 52.00, Sira Taluk.

No.	Description of work	Unit	Quantity	Rate
	I. *Bund at R. L. 57.00.*			Rs. a. p.
1	Clearing jungle and cutting grips to the bund	Grades	39	3 0 0
2	Earthwork to bund including lead and lift with watering and tamping using soil got from stuff and approach clearing	C.yd.	12,970	0 5 0
3	Turfing	S.yd.	12,960	0 1 0
4	New rough stone work with lead of 2½ miles	C.yd.	925	2 0 0
5	Earthwork excavation of foundation for revet (chargeable to bund).			
6	Removing and resetting old revetment with new jelly	L. S.		
7	Providing and fixing new grade stones including dressing, carving figures and painting	Each grade stone.	8	3 0 0
8	Removing, refixing old grade stones with its position	,,	32	0 4 0
9	Covering figures and painting old grade stone	,,	32	0 8 0
10	Providing and fixing a new Register No. stone including carving and painting	Each	1	5 0 0
11	Do gauge stone	,,	1	20 0 0
12	Painting and figuring old B. M. stone	,,	2	0 6 0
	II. (*a*) *Raising the left waste weir to R. L.* 52.00.			
1	Earthwork excavation for foundation of body wall and return, approach and draft foundation of approach and left training bank (chargeable to bund).			
2	Dismantling coping and brick masonry	C.ft.	113	0 0 6
3	Burnt brick in surki mortar	,,	1,174	0 5 0
4	Plastering with surki mortar	Sqr.	7.00	3 12 0
5	Pointing with cement	,,	3.31	4 0 0
6	Concrete backing (cement mortar) 1 : 4	C.ft.	200	0 4 6
7	Cement plastering ¾″ thick	Sqr.	2.00	12 0 0
8	Burnt stone slabs dressed and fixed 6″	S.ft.	244	0 8 0
9	Removing and resetting old burnt stone slabs in cement mortar (1 : 4)	,,	116	0 2 0
10	New rough stone work with new jelly with 2 miles lead	C.yd.	60	2 0 0
11	Old rough stone work with new jelly	,,	6	0 14 0
12	Forming new training bank	,,	53	0 2 6
13	Clearing jungle and unforeseen charges	L. S.		
	II. (*b*) *Raising the right waste weir to R. L.* 52.00.			
1	Dismantling old coping and body wall	C.ft.	57	0 0 6
2	Burnt brick in surki mortar	,,	379	0 5 0
3	Concrete in cement mortar (1 : 4)	,,	450	0 4 6
4	Plastering with surki mortar	Sqr.	5.00	3 12 0
5	New burnt stone slabs 6″ dressed and fixed with pin joints	S.ft.	517	0 8 0
6	Removing and refixing old burnt stone slabs (1 : 4) cement mortar	,,	130	0 2 0
7	Pointing with cement	,,	5.02	4 0 0
8	Removing and resetting apron with new jelly	C.yd.	138	0 14 6
9	Jelly wedging to the other portion of apron and extra filling required for bringing apron to 1 in 6	C.yd.	25	1 0 0
10	Clearing jungle, earthwork to training bank and excavation of foundation for extension of returns and unforeseen charges	L. S.		
	III. *Repairs to Sluices.*			
1	Raising gibbet cistern walls and sundry repairs	L. S.		
2	Providing plugs with iron rods and locking arrangements	Each	2	25 0 0
3	Improving and repairing the aqueduct across kodi halla of right sluice channel	L. S.		

P. RAJAGOPALAN,
Executive Engineer.

6 b

CHITALDRUG DIVISION.

Notification dated 11th January 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 5th February 1940, for Additional Accommodation in the District Lock-up at Chitaldrug.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for the Additional Accommodation in the District lock-up, Chitaldrug." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 125 (Rupees one hundred and twenty-five) in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money in the first instance and 5 per cent will be reserved in bills up to 10 per cent. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers as wish to be present on 5th February 1940 at 4 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug on all working days between 11 A.M. and 5 P.M. and the Tender Notification may be obtained from that officer on payment of Re. 0-4-0.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the 15th of June 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 10 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

23. Chamundi Brand cement alone to be used.

24. All lumpsum items will be paid for as per lowest schedule of rates after measuring the the details of work done.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Estimate for the additional accommodation in the District Lock-up at Chitaldrug.

No.	Items of work	Estimate			Tender rate	
		Per	Rate	Quantity	In figures	In words
	I. *Extending Ward No. 3 on the eastern side.*		Rs. a. p.		Rs.	Rs.
1	Earthwork excavation	C.yds.	0 3 0	22		
2	Laying stone jelly concrete in lime mortar	C.ft.	0 3 6	203		
3	Size stone in lime mortar for foundation	,,	0 4 0	464		
4	Burnt brick in mortar	,,	0 4 0	1,257		
5	Burnt stone slabs 6″ thick and fixed in lime mortar	S.ft.	0 6 6	115		
6	Providing T. W. windows with outside shutter 1½″ thick with ¾″ bars 4″ C to C, central flat iron bars, with hooks, etc., complete	,,	1 12 0	63		
7*a*	T. W. door with 2″ thick shutters with iron bars, etc., complete	,,	1 12 0	30		
7*b*	Do ordinary door for bath-room	,,	1 8 0	25		
8	T. W. wrought and put up including wood oiling	C.ft.	5 0 0	35		
9	Mangalore tiled roofing with 2″×1″ T. W. reepers	Sqr.	30 0 0	5·38		

No.	Items of work	Estimate			Tender rate	
		Per	Rate	Quantity	In figures	In words
			Rs. a. p.		Rs.	Rs.
10	Providing ridge tiles fixed in lime mortar and cement pointed	R.ft.	0 8 0	22		
11	Providing cornice at the roof level	,,	0 4 0	68		
12	Providing mortar bands	,,	0 2 0	48		
13	Flooring with $1\frac{1}{2}''$ cement concrete over 3" lime concrete including plastering, etc., complete	Sqr.	19 0 0	3·00		
14	Plastering with lime mortar	,,	3 4 0	14·81		
15	Pointing with cement mortar alround basement	,,	4 0 0	0·95		
16	White-washing as per plastering (item No. 14)	,,	0 4 0	14·81		
17	Providing and fixing ceiling planks of T. W. $\frac{3}{4}''$ thick	S.ft.	0 7 0	330		
18*a*	Constructing raised platforms to serve as bed brick in mortar	C.ft.	0 4 0	91		
18*b*	Cement plastering for sides and pillow portion $\frac{3}{4}''$ thick	Sqr.	8 0 0	1		
19	Filling in basement with gravelly soil with a lead of $\frac{1}{2}$ mile	C.yd.	0 8 0	32		
	I. (*a*) *Providing a bathroom for above ward.*					
1	Earthwork excavation	C.yd.	0 3 0	4		
2	Laying stone jelly concrete in lime mortar	C.ft.	0 3 6	53		
3	Size stone in lime mortar	,,	0 4 0	105		
4	Burnt brick in lime mortar	,,	0 4 0	353		
5	Providing T. W. window with iron bars and outside shutters, central flat iron, etc., complete	S.ft.	1 12 0	12		
6	Providing 6" burnt stone sills and lintle slabs	,,	0 6 6	13		
7	T. W. wrought and put up including wood oiling	C.ft.	5 0 0	5		
8	Providing ceiling plank of T. W. $\frac{3}{4}''$ thick	S.ft.	0 7 0	45		
9	Mangalore tiled roofing over $2'' \times 1''$ reepers	Sqr.	26 0 0	0·81		
10	Providing cornice at the sides	R.ft.	0 4 0	18		
11	Do mortar bands	,,	0 2 0	18		
12	Flooring with cement concrete $1\frac{1}{2}''$ thick over 3" lime concrete, plastering, etc., complete	Sqr.	19 0 0	0·36		
13	Plastering with lime mortar	Sqr.	3 4 0	4.08		
14	White-washing as per plastering above	,,	0 4 0	4.08		
15	Constructing a sink in the bath-room	As per actual work				
16	Providing a cistern outside	Do				
	II. *Extending the female ward on the western side.*					
1	Dismantling the existing bath-room attached to the female ward and cross-wall between	As per actual work				
2	Earthwork excavation	C.yd.	0 3 0	10		
3	Laying stone jelly concrete in lime mortar	C.ft.	0 3 6	75		
4	Size stone in lime mortar	,,	0 4 0	150		
5	Burnt brick in lime mortar	,,	0 4 0	268		
6	Burnt stone slabs 6" thick dressed and fixed	S.ft.	0 6 6	76		
7	Providing T. W. windows with $\frac{3}{4}''$ iron bars and outside shutters, central flat iron, etc., complete	,,	1 12 0	63		
8	Providing T. W. doors	,,	1 12 0	55		

No.	Items of work	Estimate			Tender rate	
		Per	Rate	Quantity	In figures	In words
			Rs. a. p.		Rs.	Rs.
9	T. W. wrought and put up with wood-oiling	C.ft.	5 0 0	35		
10	Mangalore tiled roofing with 2″×1″ T. W. reepers	Sqr.	26 0 0	4.88		
11	Providing ridge tiles fixed in lime mortar including cement pointing	R.ft.	0 8 0	20		
12	Providing cornice	,,	0 4 0	39		
13	Providing mortar bands	,,	0 2 0	50		
14	Flooring with 1½″ cement concrete over 3″ lime concrete including plastering, etc., complete	Sqr.	19 0 0	2.93		
15	Plastering with lime mortar	Sqr.	3 4 0	10.50		
16	White-washing as per plastering above	,,	0 4 0	10.50		
17	Pointing with cement mortar	,,	4 0 0	0.34		
18	Providing and fixing T. W. ceiling planks ¾″ thick	S.ft.	0 7 0	302		
19*a*	Constructing raised platforms to serve as beds in brick mortar	C.ft.	0 4 0	91		
19*b*	Cement plastering to above ¾″ thick, etc.	Sqr.	8 0 0	1		
	II. *(a) Providing a bathroom to the above extension.*					
1	Earthwork excavation	C.yd.	0 3 0	4		
2	Stone jelly concrete in lime mortar	C.ft.	0 3 6	53		
3	Size stone in lime mortar	,,	0 4 0	103		
4	Burnt brick in mortar	,,	0 4 0	237		
5	Providing T. W. windows complete	S.ft.	1 12 0	12		
6	Providing 6″ B. slabs	,,	0 6 6	13		
7	Teakwood wrought and put up	C.ft.	5 0 0	5		
8	Providing T. W. ceiling planks ¾″ thick	S.ft.	0 7 0	45		
9	Roofing with Mangalore tiles, etc.	Sqr.	26 0 0	0.81		
10	Providing cornice at ends	R.ft.	0 4 0	18		
11	Providing mortar bands	,,	0 2 0	18		
12	Flooring with 1½″ cement concrete, etc.	Sqr.	19 0 0	0.36		
13	Plastering with lime mortar	,,	3 4 0	4.08		
14	White-washing as per plastering	,,	0 4 0	4.08		
15	Constructing a sink	As per	actual work			
16	Constructing a cistern		Do			
	III. *Constructing a special ward for females on the western side.*					
1	Dismantling the existing wall and terrace of Contractor's room	As per	actual work			
2	Earthwork excavation	C.yds.	0 3 0	19		
3	Laying stone jelly concrete in lime mortar	C.ft.	0 3 6	144		
4	Size stone in lime mortar for foundation	,,	0 4 0	288		
5	Burnt brick in lime mortar	,,	0 4 0	706		
6	Burnt stone slabs 6″ thick dressed and fixed	S.ft.	0 6 6	61		
7	Providing T. W. windows with iron bars, flat iron and outside shutters, etc., complete	,,	1 12 0	47		
8	Fixing the released doors	Each	1 0 0	2		
9	Teakwood wrought and put up with wood-oiling	C.ft.	5 0 0	21		
10	Mangalore tiled roofing with 2″×1″ T. W. reepers, etc., complete	Sqr.	26 0 0	4.13		
11	Providing ridge tiles fixed in lime mortar including cement pointing	R.ft.	0 8 0	16½		
12	Providing cornice	,,	0 4 0	58		
13	Providing mortar bands	,,	0 2 0	48		

No.	Items of work	Estimate		Tender rate		
		Per	Rate	Quantity	In figures	In words
			Rs. a. p.		Rs.	Rs.
14	Flooring with 1½″ cement concrete over 3″ lime concrete including plastering, etc., complete	Sqr.	19 0 0	2.25		
15	Plastering with lime mortar	,,	3 4 0	10.96		
16	White-washing as per plastering above	,,	0 4 0	10.96		
17	Plastering with cement mortar	,,	8 0 0	0.80		
19	Providing T. W. ceiling planks ¾″ thick	S.ft.	0 7 0	223		
19	Constructing raised platform for bed, brick in mortar	C.ft.	0 4 0	108		
	III. (*a*) *Providing bathroom for the above.*					
	Details *vide* II (*a*)					
	IV. *Constructing an additional room for the contractor by extending on the western side of the approver's room.*					
	(In place of room to be dismantled.)					
1	Earthwork excavation	C.yd.	0 3 0	7		
2	Laying stone jelly concrete in lime mortar	C.ft.	0 3 6	62		
3	Size stone in mortar	,,	0 4 0	119		
4	Burnt brick in lime mortar	,,	0 4 0	167		
5	Burnt stone slabs 6″ thick dressed and fixed	S.ft.	0 6 6	39		
6	Providing T. W. doors with batten shutters, etc., complete	,,	1 8 0	25		
7	Providing T. W. windows without side shutters and ¾″ iron bar	,,	1 12 0	27		
8	Teakwood wrought and put up with wood-oiling	C.ft.	5 0 0	43		
9	Roofing with Mangalore tiles over 2″×1″ T. W. reepers	Sqr.	26 0 0	3.72		
10	Flooring with 1½″ cement concrete over 3″ lime concrete including cement plastering, etc.	,,	19 0 0	2.36		
11	Plastering with lime mortar	Sqr.	3 4 0	3.05		
12	White-washing	,,	0 4 0	8.32		
	V. *Other items.*					
1	Raising the compound wall by 6′ burnt brick in mortar	C.ft.	0 4 0	250		
2	Plastering with lime mortar for raised portion	Sqr.	3 4 0	6.40		
3	Painting doors and windows and white-washing, etc.	(As per actual work)				

Notification dated 15th January 1940.

It is notified for the information of the travelling public that the undermentioned Travellers' Bungalows will not be available for travellers, on dates noted against them, as they are reserved for Government purposes.

Davangere T. B. ... From 26th January 1940 to 31st January 1940 (both days inclusive).

Chitaldrug T. B. ... From 28th January 1940 to 3rd February 1940 (both days inclusive).

B. TIRUMALACHAR,
Executive Engineer.